



Calhoun: The NPS Institutional Archive
DSpace Repository

Theses and Dissertations

1. Thesis and Dissertation Collection, all items

1949-06

The design of an all-welded, 120' span, two lane, deck highway bridge

Cassidy, Earle Morrow; Otto, Carl Warren

Troy, New York; Rensselaer Polytechnic Institute

<http://hdl.handle.net/10945/6362>

Downloaded from NPS Archive: Calhoun



<http://www.nps.edu/library>

Calhoun is the Naval Postgraduate School's public access digital repository for research materials and institutional publications created by the NPS community. Calhoun is named for Professor of Mathematics Guy K. Calhoun, NPS's first appointed -- and published -- scholarly author.

Dudley Knox Library / Naval Postgraduate School
411 Dyer Road / 1 University Circle
Monterey, California USA 93943

THE DESIGN OF AN ALL-WELDED,
120' SPAN, TWO LANE,
DECK HIGHWAY BRIDGE

EARLE MORROW CASSIDY
CARL WARREN OTTO

Thesis
C28

Thesis
C28

Library
U. S. Naval Postgraduate School
Annapolis, Md.

THE DESIGN OF AN ALL-WELDED,
120' SPAN, TWO LANE, DECK HIGHWAY BRIDGE

By

Earle Morrow Cassidy

Carl Warren Otto

Submitted to the Faculty of
Rensselaer Polytechnic Institute
in partial fulfillment of the
requirements for the Degree of
Master of Civil Engineering

Troy, New York

June, 1949

ACKNOWLEDGMENT

The authors are gratefully indebted to Dr. J. Sterling Kinney for his aid and guidance throughout the preparation of this paper. And to Mr. A. Amirikian the authors express their sincere appreciation for his valuable criticisms and suggestions.

THE

The subject of this paper is the
 the history of the people of the
 the history of the people of the
 the history of the people of the
 the history of the people of the
 the history of the people of the

TABLE OF CONTENTS

	Page
Introduction	
Including a brief history of bridge welding, some general design considerations, and an evaluation of the structure.	4
Design Procedure	
With emphasis on the particular problems considered in the design of each structural component.	12
Design Computations	
With reference to preliminary designs and their shortcomings, and a tabulation of the final design calculations.	26
Bibliography	62
Index	64
Appended Drawings	
Including plans, elevations, cross-sections, and details of all important members and connections.	

INTRODUCTION

In the years preceding World War II welding was considered a structural outcast. The several committees and associations responsible for the standard specifications and procedures viewed welding as adequate for minor structural fabrication, where stresses were for all practical considerations predominately static. The dynamic load properties of welded connections were untested, and the construction field felt a vague understandable fear of its use in multi-million dollar buildings and bridges.

Today, the field testing of welding is over. Military and industrial application of welding to our gigantic war machine needs gave convincing evidence to engineers that a welded joint, properly understood, could do its job cheaply and successfully. Now all that remains is to overcome the inertia of the specifications and codes.

In the latest printing of the American Association of State Highway Officials' Standard Specifications for Highway Bridges (1944), welding is classified as permissible on incidental parts of the structure only. Warn the specifications, "Welding is not recommended in main members or their connections where the failure of the weld would endanger the stability of the structure." What a blow to the proponents of welding! While these A.A.S.H.O. standards serve as a guide for most highway bridge construction, some states in the years since 1940 have recognized the value of welding as an economic fabrication medium and have assumed responsibility for the construction of several welded highway bridges. California and New York, with a great number of miles of highways and

numerous bridges to accommodate them, have been leaders in the promotion of the welded structure.

At this time the most popular application of bridge welding technique is to the deck girder and the rigid frame types. These are all of moderate spans in the neighborhood of sixty to eighty feet, seldom exceeding 100 feet. Both of these bridge types present a neat unobstructed roadway for the motorist utilizing them. In elevation, also, they tend to give a pleasing architectural effect if such an effect is considered in design. For this reason their use is extensive at grade eliminations and for suburban stream crossings. When considered architecturally, the fundamental cleanliness of shape and joints of a welded structure often eliminate the necessity for a complex exterior veneer of stone or concrete to dress up the bridge.

An additional economic advantage is offered by the use of a composite steel beam and concrete slab. In this design method the concrete floor slab of a deck-type bridge acts as a part of the compression flange of each of the welded girders. All that is required for such composite action is an adequate means of resisting the shear between the steel beam and the concrete. Shear keys, fastened to the beam flange and imbedded in the concrete, are the answer. So far, riveted shear keys have not proved satisfactory; all their difficulties have been overcome by use of a welded shear key.

Considering these facts, it is apparent that a bright future exists for the welded bridge. It can successfully compete with riveted bridges using old-style design and materials that were developed for the peculiar

needs of riveted work. And, hamstrung by many of the old specifications, it can still prove itself a cheaper, better-looking, longer-lasting bridge.

Perhaps the welded bridge could be much better yet, if it were designed from scratch as a welded structure, not just a bridge for which welds are substituted for rivets. This is the current thought that drifts through the industry today. A good many technical articles and several competitions have stressed the desirability of breaking away from the old patterns of riveted construction. The optimum welded bridge may have vastly different structural characteristics than that which is considered correct today. Only design investigation of the remotest possibilities in all their myriad combinations will produce the answer.

In an effort to advance one step toward that goal this thesis has been undertaken.

The design of a welded bridge, discarding the familiar specifications, procedure, and materials, is a tedious undertaking. As a steadying influence, the authors elected to design the structure according to the competitive restrictions of the James F. Lincoln Arc Welding Foundation's Welded Bridges of the Future award program for 1949. It was felt that if the finished design had sufficient merit it could be submitted as a contest entry with the performance of the additional work required for detailed drawings and cost estimates.

For this design the bridge was classified as a two-lane deck highway bridge supported on piers 120 feet apart. The design of the piers or abutments was not considered. The requirements of the steel satisfied A.S.T.M.-A7-46 specifications. For proportioning members, determining

allowable unit stresses, and sizing welds used in the fabrication the 1947 edition of the Standard Specifications for Welded Highway and Railroad Bridges of the American Welding Society were followed. Contest specifications designated the loadings to be applied to the designed structure. Those other features of the design normally considered by specifications when designing a riveted bridge were evaluated with reference to a welded structure. The authors attempted to judge logically the necessity for the use of these old specifications. Any that should apply or seemed to apply were given consideration in the solution of the problem.

A deliberate attempt was made to incorporate into the bridge structure new or seldom used shapes. This has resulted in a structural system which, to the knowledge of the authors, is as yet untried. It is fundamentally a backbone-and-rib system, utilizing a single box-shaped girder as the primary vertebrae resisting shear, bending, and torsion. Transmitting loads to the girder are the eight pairs of ribs or floor beams. These beams have a wide-flange type cross-section and are cantilevered from the girder to give support to the floor system and its stringers. To economically utilize the metal in these floor beams their vertical longitudinal section has been designed as a wedge section, a section suggested only recently by A. Amirikian for use in mill buildings, shops, warehouses, and similar structures formerly requiring rigid frames and trusses to span large floor areas.

Architecturally, the thinnest possible elevation that was presented to the eye seemed to be desirable. The use of the wedge beams tends to accentuate this thinness from almost any position that the observer might

select. In order to break the otherwise long (120 feet) straight line of the bottom flange of the girder, the flange is shaped to a parabolic curve rising three feet at mid-span. This is also an economical solution for fixity of the ends of the girder, a condition incorporated in the girder design. As a result of these features, the bridge presents a graceful, willowy silhouette that is ideally suited for grade-crossing eliminations and stream crossings in suburban areas.

The value of the torsional shear that would be applied was much smaller than first guesses had estimated. No previous literature was located to give any hint as to the magnitude of this shear and early in the design there was some doubt in the authors' minds as to the ability of a reasonable girder section to resist the maximum torque condition.

A modern two-lane 24-foot highway is assumed to be served by the bridge. As recommended by safety considerations, the bridge roadway is widened to 26 feet between curbs and 29 feet clear between guard railings. The curbs are flared at the approaches to prevent vehicles from striking the guard rail end posts. No sidewalks were designed, although they may be installed without increasing the size of any of the present main structural members. Occasional pedestrians may cross by using the 18 inch curb top.

By trying small scale elevations of the bridge and using different panel lengths for each, a seven-panel design was chosen as most pleasing architecturally. The standard panel is 17 feet. To overcome the shortening illusion of the solid vertical abutment wall upon the end panels, the end bearing connection was placed beyond the last floor beam.

A light-weight floor system that utilizes welding to fasten it to

the stringers is the U. S. Steel Company's Armored I-Beam-Lok. It is a steel grid floor filled with low-grade concrete. It is tack welded to each stringer to give a structure strong enough to resist the lateral forces applied by wind and lateral loads. The floor stringers run longitudinally at an assumed spacing of 5 feet 3 inches. By using longitudinal stringers any permanent deflection of the floor between stringers will not destroy the smooth riding quality built into the floor. An attempt was made to fasten the floor and the stringer together to act as composite beams. Investigation proved that this was impractical. Instead, each stringer is designed as continuous over the seven panels.

The roadway loadings as specified by the contest specifications are identical to the H20-44 loadings given by the A.A.S.H.O. in their 1944 specifications.

Field erection of this bridge is felt to be an additional advantage. If conditions permit, the girder will be completely shop assembled and transported to the site in one piece. There it will be installed and used as the base for all further erection. With the girder up the floor beams are erected in pairs by use of a wide flange erection piece that straddles the top of the girder between the beams and holds them in place for welding. Before welding the stringers rest on the top flanges of the beams without the use of special fastenings. As soon as the stringers are set, the steel grid may be laid and immediately used as a working platform for the remainder of the erection and finishing.

Looking over the completed design, the authors feel that they have accomplished at least in some measure the following: First, the

sections of the cantilever beams, the girder, and the floor system are particularly adapted to welding practices. Second, complete use is made of the material. Each member was proportioned throughout its length, with due regard to costs, for maximum allowable stress. Third, the total dead load of the structure is kept to a minimum and compares favorably with the designed value of live load that it will support. Fourth, the bridge is made of simple components that fit together in a simple manner.

"If a work such as a bridge be well composed constructively, whatever may be the constituent material or materials employed, and whatever may be the kind of construction, it can hardly fail to be an agreeable object for it will certainly possess the essentials to beauty in architectural composition, simplicity, and harmony. The introduction of anything not necessary to the construction, the omission of what is requisite, or the substitution of a bad expedient for a good one, will assuredly tell injuriously upon the eye, how incompetent soever the observer may be to determine the cause of the defect, or even in what the defect may consist."

Bridge Architecture

DESIGN PROCEDURE

By designing the bridge "from the top down," that is, the floor system first and the girder last, it was possible to eliminate most of the guess work involved in choosing the dead loads that were transmitted to each structural member. Only the dead weight of the member being investigated needed to be assumed for its preliminary design. Therefore, the design proceeded in this order:

Curb and Guard Rails

Floor System

Floor Stringers

Cantilever Beams

Main Girder

Bridge Seat

Ordinarily, the design of the welded connections was not considered at the time the member was investigated. These weld sizes and details of their application were made a part of the detail drawings and design of them was done at that time.

In the following discussion reference will be made to all the assumptions made in the design of each structural component. However, only that assumption that finally ruled the design method will be included in the design computations that are tabulated in the next section of this paper.

When reading through the explanation of the design procedure, it may be helpful to refer to the drawings in the appendix. Adequate details have been prepared for all portions of the structure.

CURBING AND GUARD RAILS

It was felt that adequate attention is too often lacking in the design of curbs and railings. Well chosen proportions for the railing may add much to the fundamental gracefulness of the slim horizontal bridge lines. Conversely, a hastily accepted railing design may upset the whole balance of the bridge.

Both curbs and railings were designed in accordance with the American Institute of Steel Construction folder, "Bridge Railings, Their Design and Construction." The distance between curbs is two feet greater than the approaching highway pavement width. A curb nine inches high is used, which will deflect a car and yet not catch fenders or running boards. To provide a substantial curb a horizontal force of 500 pounds per lineal foot was applied at the top of the curb.

The inside railing faces are set back eighteen inches from the curb line. A smooth railing surface is presented to traffic. On the lower rail a horizontal design force of 500 pounds per lineal foot was applied. The two top rails had a horizontal force of 150 pounds per lineal foot applied. A vertical force of 100 pounds per lineal foot was applied to each rail. The spacing of railings was chosen to give a height that did not harmfully obstruct the motorist's view. Yet it is adequate for safety and complements the gracefulness of the bridge's elevation.

To balance the upper and lower portions of the bridge as viewed in elevation it was necessary to space the vertical railing posts on 8 foot 6 inch centers, which is equivalent to one-half a panel length. These posts are anchored to the exterior floor stringers at each panel point and mid-panel point.

A molding of light gage metal extends from the curb level to just below the cantilever beam's bottom flange on the outside of the railing and serves to finish the outside edge of the roadway.

10405

FLOOR SYSTEM

A steel grid, concret--filled, flooring was chosen for its advantages of lightness, strength, long life, economy, and ease of installation. The saving in weight is not a small item. The 3 inch depth chosen, with its 1 inch bituminous wearing surface, weighs only 60 pounds per square foot. If a normal concrete slab were laid, the depth including wearing surface would be at least 10 inches and would weigh 125 pounds per square foot. The saving in floor dead load is, therefore, in excess of 50 per cent, a considerable item when the floor area amounts to more than 3100 square feet as it does in this bridge. This reduced dead load results in a decrease in size of all other structural members, stringers, beams, and girder. Hence, a lighter, more graceful bridge is possible. Although an economic study is difficult for the authors to make, it is felt that the added cost of the steel floor system is more than balanced by a saving in concrete forms and weights of material supplied for the other structural components.

Ease of installation is an important advantage of the steel grid floor. It reaches the bridge site already cut to the proper lengths and widths and with openings cut as necessary for drains. It rests directly on the upper flanges of the stringers and is welded to them to provide a rigid network of steel at the floor level to resist lateral and longitudinal loads.

During erection the steel grid is laid and welded to the stringers. By using United States Steel Armored I-Beam-Lok, light gage metal form strips fit between the main beams of the flooring on its under side and

act as forms for the concrete and as a protection for the underside of the floor. These strips are shop assembled and welded to the floor system. The concrete may be poured from transit-mix trucks running onto the bridge over the steel grid.

The stresses resulting from wheel load concentrations on the floor system and the influence of the distribution of these loads on the moments studied has been based on the theory proposed by Prof. H. W. Westergaard, of the University of Illinois, and modified by the Bureau of Public Roads. These modifications were developed to simplify the design computations for the two types of moment conditions; first, for bridge floor slabs with main reinforcement parallel to the direction of traffic; and second, main reinforcement transverse to the direction of traffic. This second condition was chosen for the design.

In this bridge the floor was made continuous over several supports and is firmly welded to the stringer flanges to produce for practical considerations a fully restrained condition. To allow for some flexibility all stresses were computed for an end restraint of 75 per cent.

LONGITUDINAL FLOOR STRINGERS

To support the floor a system of longitudinal stringers was used. This allows the sag of the floor to be parallel to the traffic travel and does not hinder the smooth riding characteristics of the bridge. The normal span of the stringers between the cantilever beams is 17 feet. Any typical cross-section contains four stringers, two on each side of the centerline. They are spaced 7.25 feet and 12.50 feet, respectively, from the centerline. The main girder also acts as support for the floor, handling the loads over the center section of the traffic area.

Three alternative designs were considered. First, the feasibility of composite action of the stringer and a portion of the concrete in the floor immediately above was considered. By assuming the designed floor depth in combination with various beam sizes, stresses were computed by transformed section analysis. Since the concrete stresses had to be superimposed upon those stresses already existing because of slab action, the actual allowable stress in the concrete was low. This meant that the floor would have to be made thicker to increase the concrete area and the concrete stress available to resist this composite beam action. The gain in weight of the thickened slab could not be regained in a similar saving in weights of the four stringer sections. Therefore, this alternative was abandoned.

The second design was based on simple beam action for each stringer. This gave a reasonable section for the stringers and was kept in reserve in case the stringer-to-beam connection became unwieldy. After the design of the beams, it became apparent that this solution was not necessary.

The final alternative was to consider the stringers as continuous over the entire seven panel lengths of the bridge. Any splices are made where study showed that moment values were low. Normally this is considered to be about one-fifth of the panel length from any support. Using such a long continuous beam, it was uncertain whether the lane loadings or the truck loadings as specified would produce the greater moments. Investigation showed that moments over the supports were greater for the lane loadings. The mid-span moments, however, were greater for the truck loadings, and these moments ruled the design of the stringer.

A slight increase in weight per foot was allowed in order to reduce the stringer depth to a practical minimum. This increase amounted to 6 pounds per foot in the three center panels and 4 pounds per foot in the four exterior panels over the weights of the most economical sections. This is an over all weight increase of about 2200 pounds in the bridge. Interior and exterior stringers were made the same since the curb position allowed the same loads to come onto the exterior stringer as were used for interior stringer design. Ordinary wide-flange sections were chosen. The loads applied made such a section ideal in resisting the generated moments. The floor fits snugly on the top flange; the bottom flange rests upon the cantilever beam and is welded to it. No difficult framing was needed.

CANTILEVER FLOOR BEAMS

The use of the wedge beam section for the cantilever floor beams was chosen as the simplest of several shapes that offered themselves for this structural member. At first, a tapered box section was considered to be more attractive to the observer. However, this type of section had no structural advantages, and it had the important disadvantage of being an expensive fabrication and erection job.

Another consideration was the built-up section consisting of a web plate and two flanges, with the lower flange bent to some curved profile, most probably parabolic. This lower curve would add gracefulness to the underside of the bridge and would possibly conform to the requirements of the applied moments. This design was discarded because of the added cost of fabrication with only small saving in the weights of steel over the triangular wedge shape.

As previously mentioned in the early pages of this report, the wedge beam has the advantages of attractiveness, lightness, and economical use of metal to resist the shears and moments. A standard rolled wide flange section was chosen as the parent material. It was split along its web in a straight diagonal line for the full length of one cantilever beam. This diagonal cut was so proportioned that the webs are rejoined along the cut after one half of the beam is reversed end for end. With the proper design it was possible to make the section modulus curve of the newly welded wedge parallel to the required section modulus of the cantilever beam. And this fabrication requires but one flame cutting and one shop weld for each wedge beam.

It was feared that the wedge might not have the required stiffness

to resist excessive deflection tendencies. To investigate the deflection it was necessary to make a combined graphical and analytical solution of the beam by the slope deflection method. The deflection was not critical, indicating that the extra stiffness near the support more than compensated for the beam's flexibility near its free end.

MAIN GIRDER

For resistance to torsional shear the most efficient cross-section that could be applied to this bridge was the symmetrical box with rounded corners. However, the material in this cross-section also was called upon to resist transverse shear in the web portions and direct stresses in the flange portions. This led to the adoption of a box section with rounded corners that had very heavy flanges to develop the necessary moment of inertia to resist the bending moments, with only light web pieces to resist shear.

Preliminary studies indicated that the torsional shear would be small compared to the transverse shear and bending stresses. Consequently, the girder was designed for these latter forces only, and an allowance was made in proportioning the members to keep the stresses slightly below their limiting values. When these stresses were later combined by principal stresses with the torsional shear, the total stresses were still below their limits.

Rounded corners were used for two purposes. First, these corners, made with adequate radii, eliminate any concentration of the torsional stress as it flows around the cross-section. These concentrations when caused by square corners are not properly investigated, and leading authorities disagree on the increase to be assumed. Most allow a 150 to 200 per cent increase. Second, rounded corners eliminate the use of fillet welds at points of stress concentration, a condition prohibited by welding specifications.

The girder cross-section was designed for moment at the end supports and at the center of the span. At these points the steel was proportioned

so that one size of plate is used for both flanges and another size for both webs throughout the entire length of the girder. Any necessary increase in moment of inertia was handled by the parabolic curve of the bottom flange, which increased the depth of the girder from 5 feet at the mid-span to 8 feet at the supports. These design dimensions for the parabola were influenced by the appearance in elevation as well as by the requirements for moment of inertia. Fortunately, the two conditions did not contradict one another.

For negative moment over the supports 100 per cent fixity was assumed, for this gave the worst condition. For maximum positive moment at mid-span the rigidity was reduced to 75 per cent to allow for any small deformations of the bridge seat. In the first solution of the girder it was necessary to consider it as being of uniform cross-section throughout and to be simply supported. Under these assumptions four loading conditions were tested, all of which gave practically identical results. Then the value of moment chosen was modified according to the effect of end restraint on moments existing at the supports and at mid-span. These modified moments were designated as the trial design moments, from which the first proportioning of the girder was made.

With the girder dimensions chosen the moment of inertia of sections along the span was computed. The cube root of all these moments of inertia were plotted against distance along the girder. The resultant curve approached a parabola so that it was considered safe to use the Handbook of Frame Constants as published by the Portland Cement Association for calculation of the fixed end moments.

For the conditions along the girder were examined for all conditions of unbalanced loading. From this inspection it was shown that the

torsional shear could vary from zero to one definite maximum, and that this same maximum could exist at any point along the girder cross-section, the maximum shear shifting as the maximum unbalanced loads shifted.

BRIDGE SEAT

Four sometimes incompatible functions had to be performed by the bridge seat in order that it resist the forces brought to it by the main girder. First, it was to carry the vertical thrusts to the pier or abutment. Second, it had to resist the end moments, that is, it must be rigid in the plane of the longitudinal centerline of the bridge. Third, it had to resist the transverse torque by being rigid in a transverse plane. Fourth, it was to allow for the expansion of the girder over the specified temperature ranges expected. It is believed that the joint as designed satisfies all these conditions and is still not overly complex.

DESIGN COMPUTATIONS

CURB AND RAILINGS

CURB

Assume a curb 9 inches high. Support the inside of the curb on the floor over the exterior stringer. Support the outside edge of the curb on a channel section running between railing posts.

Loads.

Horizontal -- 500 lbs. per foot of curb

Vertical -- Dead Load -- 169 lbs. per foot of curb

Live Load -- One front wheel of design truck
or 4000 lbs. placed critically

Shear between curb and flooring.

$H = 500$ lbs. per foot

Steel area required to resist shear = $\frac{500}{13000} = 0.037$ sq. ins.

Channel section.

Assume $\frac{1}{2}$ of wheel load and $\frac{1}{2}$ of dead load are supported by channel and the remainder supported on exterior stringer.

Assume channel simply supported at each railing post.

Moments.

$$\text{Dead Load. } M = \frac{wl^2}{8} = \frac{169 \times 8.5^2}{2 \times 8} = 762 \text{ ft. lbs.}$$

$$\text{Live Load. } M = \frac{Fl}{4} = \frac{4000 \times 8.5}{2 \times 4} = 4250 \text{ ft. lbs.}$$

$$\text{Impact. } \frac{50}{8.5 + 125} = 0.375$$

$$\text{use } 0.30 \quad 4250 \times .30 = 1275 \text{ ft. lbs.}$$

$$\text{Total Moment. } 6237 \text{ ft. lbs.}$$

$$\text{required Section Modulus} = \frac{6237 \times 12}{18000} = 4.19 \text{ cu. ins.}$$

Use a 6 x 2 x 8.2 lb. channel; $b = 4.3$ cu. ins.

LOWER RAILING

Span. 8.5 ft.

Live Loads.

Horizontal -- 500 lbs. per foot

Vertical -- 100 lbs. per foot

Shear.

$$\text{Horizontal -- } 500 \times \frac{8.5}{2} = 2125 \text{ lbs}$$

$$\text{Vertical -- } 100 \times \frac{8.5}{2} = 425 \text{ lbs}$$

Moment.

$$\text{Horizontal -- } 500 \times \frac{8.5^2}{8} = 4510 \text{ ft lbs}$$

$$\text{Vertical -- } 100 \times \frac{8.5^2}{8} = 902 \text{ ft lbs}$$

Use $f = 18000$ psi

Required Section Modulus.

$$S_h = \frac{4510 \times 12}{18000} = 3 \text{ cu ins}$$

$$S_v = \frac{902 \times 12}{18000} = 0.602 \text{ cu ins}$$

Try a cross-section 6" x 2" x 3/16"

$$I_v = 2Ax^2 + 2 \frac{b h^3}{12} = 2 \times 2 \times 3/16 \times 2.906^2 + 2 \times 3/16 \times \frac{6^3}{12} = 13.07 \text{ in}^4$$

$$S_h = \frac{I_v}{c} = \frac{13.07}{3} = 4.35 \text{ cu ins}$$

$$I_h = 2 \times 6 \times 3/16 \times 0.906^2 + 2 \times 3/16 \times \frac{2^3}{12} = 2.07 \text{ in}^4$$

$$S_v = \frac{2.07}{1} = 2.07 \text{ cu ins}$$

UPPER RAILING

Span. 8.5 ft.

Live Loads.

Horizontal -- 150 lbs. per foot

Vertical -- 100 lbs. per foot

Shear.

$$\text{Horizontal} -- 150 \times \frac{8.5}{2} = 638 \text{ lbs}$$

$$\text{Vertical} -- 100 \times \frac{8.5}{2} = 425 \text{ lbs}$$

Moment.

$$\text{Horizontal} -- 150 \times \frac{8.5^2}{8} = 1352 \text{ ft lbs}$$

$$\text{Vertical} -- 100 \times \frac{8.5^2}{8} = 902 \text{ ft lbs}$$

Use $f = 18000 \text{ psi}$

Required Section Modulus.

$$S_h = \frac{1352 \times 12}{18000} = 0.9 \text{ cu ins}$$

$$S_v = \frac{902 \times 12}{18000} = 0.602 \text{ cu ins}$$

Try a cross-section 6" x 2" x 1/8"

$$I_v = 2 \times 2 \times \frac{1}{8} \times 4.933^4 + 2 \times \frac{1}{8} \times \frac{6^3}{12} = 8.8 \text{ in}^4$$

$$S_h = \frac{8.8}{3} = 2.93 \text{ cu ins}$$

$$I_h = 2 \times 6 \times \frac{1}{8} \times 0.933^2 + 2 \times \frac{1}{8} \times \frac{2^3}{12} = 1.47 \text{ in}^4$$

$$S_v = \frac{1.47}{1} = 1.47 \text{ cu ins}$$

RAILING POSTS

Span. (Cantilever) 2' - 10"

live loads.

See Figure at right.

Shear.

Horizontal -- 5526 lbs

Vertical -- 3700 lbs

Moment.

$4250 \times 2.584 = 11000$ ft lbs

$1276 \times 3.83 = 4880$ ft lbs

$1700 \times 0.107 = 184$ ft lbs

Total = 16164 ft lbs

required Section Modulus.


$$S = \frac{16164 \times 12}{18000} = 10.77 \text{ cu ins}$$

Try a cross-section $4\frac{1}{2}" \times 4\frac{1}{2}" \times \frac{1}{2}"$

Area = $4 \times 4\frac{1}{2} \times \frac{1}{2} = 9$ sq ins safe for shear.

$$I = 2 \times \frac{1}{2} \times 4\frac{1}{2} \times 2^2 + 2 \times \frac{1}{2} \times \frac{4\frac{1}{2}^3}{12} = 25.0 \text{ in}^4$$

$$S = \frac{25.0}{2.25} = 11.11 \text{ cu ins}$$



FLOOR SYSTEM

WEARING SURFACE

Use a 1 inch wearing surface of concrete or of asphalt.

FLOOR SLAB

Use United States Steel 1 Beam Lok Armored slabs.

Lay flooring transverse to traffic flow.

Compute stresses by modified Westergaard theory.

Span.

Stringer spacing = 5.25 ft

Assume stringer flanges 8 inches wide.

Clear span = 5.25 ft - 8 ins = 4 ft 7 ins

Design span = $4' - 7" + \frac{8"}{2} = 4 \text{ ft } 11 \text{ ins}$

Assume a monolithic slab. Interior spans assumed to have a 75 per cent end restraint condition. Design a portion of the slab 1 foot wide.

Loads.

Dead Loads

Wearing Surface = $1 \times 1 \times \frac{1}{12} \times 150 = 12.5 \text{ lbs per foot}$

Assume 3 inch 1 Beam Lok Armored = 47.0 lbs per foot

Total = 59.5 lbs per foot

Live Loads

Truck loading rules

1 front axle of 30,000 lbs (4000 per wheel)

1 rear axle of 32000 lbs (16000 per wheel)


Impact Allowance

$I = \frac{50}{L + 125}$, where L is the design span in feet

$$I = \frac{10}{4.7 + 1.5} = 1.335 \quad \text{Use a maximum } I \text{ of } .30$$

Moments.

See sketch to right.



Positive Moment

$$\text{Dead load} = \frac{wL^2}{14} = \frac{37.5 \times 4.917^2}{14} = 133 \text{ ft lbs}$$

$$\text{Live load} = \frac{PL}{1.32L + 10} = 0.0525P$$

$$\frac{16000 \times 4.917}{2.32 \times 4.917 + 10} = 0.0525 \times 16000 = 840 \text{ ft lbs}$$

$$\text{Impact} = 0.30 \times 840 = 252 \text{ ft lbs}$$

$$\text{Total} = 840 + 252 = 1092 \text{ ft lbs}$$

Stresses resulting from positive moment

$$\text{Section Modulus of compression concrete} = 11.3 \text{ cu ins}$$

$$\text{Section Modulus of tensile steel} = 3.02 \text{ cu ins}$$

The above values are average values for I beam box.

$$\text{Concrete stress} = \frac{M}{S_c} = \frac{1092 \times 12}{11.3} = 1150 \text{ psi}$$

$$\text{Steel stress} = \frac{M}{S_s} = \frac{1092 \times 12}{3.02} = 4380 \text{ psi}$$

Low grade concrete is used to fill I beam box. For

design a value of $n = 15$ is used and the stresses allowed

are: for concrete, 1150 psi, and for steel, 18000 psi.

Concrete is assumed not to have any value in tension.

Negative Moment

$$\text{Dead load} = \frac{wL^2}{10} = \frac{27.5 \times 4.917^2}{10} = 144 \text{ ft lbs}$$

$$\text{Live load} = \frac{PL}{1.32L + 14} = 0.0525 \text{ ft}$$

$$\frac{16000 \times 4.917}{1.32 \times 4.917 + 14} = 0.0525 \times 16000 = 3000 \text{ ft lbs}$$

$$\text{Impact} = 0.30 \times 3000 = 900 \text{ ft lbs}$$

$$\text{Total} = 4044 \text{ ft lbs}$$

Stresses resulting from negative moment

$$\text{Section Modulus of compression concrete} = 56.3 \text{ cu ins}$$

$$\text{Section Modulus of tensile steel} = 2.54 \text{ cu ins}$$

$$\text{Concrete stress} = \frac{M}{S_c} = \frac{4044 \times 12}{56.3} = 861 \text{ psi}$$

$$\text{Steel stress} = \frac{M}{S_s} = \frac{4044 \times 12}{2.54} = 19000 \text{ psi}$$

The steel stress is a little over the allowable value chosen but will be adequate within the design limits of the problem.

Truck loading at 100 miles per hour loading. Truck in each panel produces 100,000 lbs. of weight.

At 100 miles per hour loading, the loadings at all points were found to be 100,000 lbs. of weight.

Results.

Direct distribution was used to solve the continuous beam, load loading, and the results were solved for all positions of loads.

Solution is given for the wall and column only, maximum moments in other panels or at other points are tabulated.

Dead loads


	A	B	C	D	E	F	G	H
	3.62 kips							
K	1	0.75	1	1	1	1	1	0.75
DF	1	0.429	0.571	0.5	0.5	0.5	0.5	0.429
	+8.7	-8.7	+8.7	-8.7	+8.7	-8.7	+8.7	-8.7
	-8.7	-4.4						+4.4
	+1.9	+2.5	+1.2					
		-0.3	-0.6	-0.3				
		+0.1	+0.1	+0.1	+0.1	+0.1	+0.1	
	0	-11.2	+11.2	-8.3	+8.3	-8.3	+8.3	-11.2

Live loads

	A	B	C	D	E	F	G	H
	16k	4k						
K								
DF								
	+34	-34	+10.1	-4.8				
	-34	-17						
	+11.5	+23.4	+11.7					
		-1.7	-3.5	-3.5	-1.7			
		+0.7	+1.0	+0.5	+0.4	+0.8	+0.8	+0.4
		-0.2	-0.5	-0.4	-0.2	-0.2	-0.2	-0.1
		+0.1	+0.1	+0.1	+0.1	+0.1	+0.1	+0.1
	0	-30.7	+30.7	+3.4	-3.4	-0.9	+0.9	+0.2

$$\text{Dead load} = 362 \times 0.1 = 36.2 \text{ lbs}$$

Live load



$$= 18.26 \text{ lbs}$$

$$\text{Impact} = 1.25 \times 18.26 = 22.83 \text{ lbs}$$

$$\text{Total} = 36.2 + 22.83 = 59.03 \text{ lbs}$$

An examination of the moments developed by the loads under the two design conditions shows that a 22 per cent reduction in moment is accomplished by use of the continuous stringer.
required section modulus.

Use a design moment of 77,000 ft lbs

$$S = \frac{77000 \times 12}{18000} = 51.5 \text{ cu ins}$$

In order to keep weight at a minimum use a

$$12" \text{ wide flange } 40 \text{ lb section; } S = 51.9 \text{ cu ins}$$

Most economical section is

$$16" \text{ wide flange } 36 \text{ lb section}$$

Web Shear Check.

$$\text{Area web} = 12 \times 0.16 = 1.92 \text{ sq ins}$$

$$\text{Shear stress} = \frac{V}{A} = \frac{2280}{1.92} = 1190 \text{ psi}$$

$$\text{Allowable shear stress} = 11000 \text{ psi}$$

Design of Floor Beam

Span.

Assume min. girder width = 5 feet

Design span = $17 - 1.5 = 15.5$ feet


Loads.

For the following solution these abbreviations will be used:

Load 1 means any load applied at free end of beam.

Load 2 means any load applied by exterior stringer.

Load 3 means any load applied by interior stringer.



Dead Loads

Floor

$$\text{Load 2} = 57.5 \times 17 \times 5.125 = 5130 \text{ lbs}$$

$$\text{Load 3} = 57.5 \times 17 \times 5.25 = 5050 \text{ lbs}$$

Railings

$$\begin{aligned} \text{Load 1} &= \text{weight of 3.5 feet} \\ &\quad \text{of railing} = 175 \text{ lbs} \end{aligned}$$

$$\text{Load 2} = \text{same as above} = 175 \text{ lbs}$$

Curb

$$\begin{aligned} \text{Load 1} &= \text{weight of concrete} \\ &\quad \text{curb and supports} = 500 \text{ lbs} \end{aligned}$$

$$\text{Load 2} = 500 \text{ lbs}$$

Stringers

$$\text{Load 1} = 4 \times 17 = 68 \text{ lbs}$$


$$\text{Load 2} = 4 \times 17 = 68 \text{ lbs}$$

No estimate made here of beam dead weight.

Live Loads

Truck loading rules.

See sketch.



$$\text{Stringer reaction} = 16 + \frac{4 \times 2}{17} = 17.1 \text{ Kips}$$

Impact Allowance

$$I = \frac{50}{12.5 + 125} = 0.364 \text{ Use a maximum } I \text{ of } 0.30$$

Moments.

Moments are computed for each foot along the beam. Using a flexure stress of 18000 psi, the required section modulus at each foot is also found.

A complete computation is given for the moment solution at the beam support.

Moment at beam support

Dead load

$$\text{Load 1} = 12.5(175 + 500) = 8440 \text{ ft lbs}$$

$$\text{Load 2} = 10.5(175 + 500 + 180 + 680) = 47500 \text{ ft lbs}$$

$$\text{Load 3} = 5.75(5500 + 680) = 31700 \text{ ft lbs}$$

$$\text{Total} = 87640 \text{ ft lbs}$$

live load

Truck

$$\text{Load } x = 12.5 \times 16710 = 208875 \text{ ft lbs}$$

$$\text{Load } y = 7.25 \times 16710 = 121062.5 \text{ ft lbs}$$

all in one car

$$\text{Load } z = 7900 \times 12.5 = 98750 \text{ ft lbs}$$

$$\text{Load } w = 2100 \times 3.5 = 7350 \text{ ft lbs}$$

$$\text{Total } = 36600 \text{ ft lbs}$$

$$\text{Impact } = 1.25 \times 36600 = 45750 \text{ ft lbs}$$

$$\text{Total } = 40250 \text{ ft lbs}$$

Section Modulus of beam support

$$S = \frac{40250 \times 12}{1800} = 268 \text{ cu in.}$$


Distance from bridge center-line	Dead load	Live load	Impact	Total	Section Modulus
3.5 feet	76500	307100	41300	476900	213
4.5	61100	262800	30600	413700	276
5.5	54500	251100	23800	351900	235
6.5	42700	172100	7100	220100	194
7.5	31300	100700	4200	136200	151
8.5	24200	114200	11300	139700	124
9.5	17600	101700	3500	122800	102
10.5	14300	77700	2300	113300	77
11.5	9200	57500	1100	68800	56
12.5	4300	34600	10400	49300	33
14	700	17600	5900	24200	18
15		15000	4200	19200	14

Wedge Beam Section.

The problem is to proportion a wedge beam whose strength in any transverse cross-section is equal to or slightly greater than that required.

Splitting a wide flange section longitudinally, flaring one half, and welding the wedges together again results in an economical wedge beam.

Split a 24" IF 54 beam as shown:



and the split 24" IF 54 beam shown:




Table - Comparison of Actual and Required Section Moduli.

Distance from bridge centerline	24" I F 84 Moment of Inertia	24" I F 84 Section Modulus	Required Section Modulus
2.5 feet	8340 ins ⁴	320 ins ³	361 ins ³
4.5	6740	324	276
6.5	5335	259	194
8.5	4436	212	124
10.5	3476	146	77
12.5	2711	96	55
15	2241	48	34

Check the increase in section modulus to handle the wedge beam dead load. Check at support only.

$$\begin{aligned} \text{Moment} &= W \times d = \text{total wt} \times \text{Dist. to BH} \\ &= 34 \times 12.5 \times 4.77 = 5020 \text{ ft lbs} \end{aligned}$$

$$\text{Section Modulus} = \frac{5020 \times 12}{13000} = 4.65 \text{ cu ins}$$

Shear.

Unsupported end

$$\text{Dead load} = 500 + 175 = 675 \text{ lbs}$$

$$\text{Live load} = 1700 + 2000 = 3700 \text{ lbs}$$

$$\text{Impact} = 0.30 \times 3700 = 1110 \text{ lbs}$$

$$\text{Total} = 5485 \text{ lbs}$$


$$\text{Web depth} = 7 \text{ ins; web thickness} = 0.47 \text{ ins}$$

$$\text{Web stress} = \frac{436}{0.47} = 927 \text{ psi}$$

Under the exterior stringer

PLOT OF M/I DIAGRAM
FOR TYPICAL FLOOR BEAM

JUNE 1949





When $\alpha = 1$, the α -mean is the arithmetic mean, the α -variance is the variance, and the α -entropy is the Shannon entropy.

$$P_{\text{max}} = 100 \times 14, \quad \lambda_{\text{max}} = 27,105 \text{ nm}$$

1900 (2000) $\frac{1}{1000} = \frac{1}{1000} \times 12 = 1.2$ (1.2) (1.2)

1900 (2000) $\times 1.2 = 2280$ (2280) (2280)


1900 (2000) = 1900 (2000) (2000)

1900 (2000) (2000) (2000) (2000)

1900 (2000) (2000) (2000) (2000)

1900 (2000)

1900 (2000) (2000) (2000) (2000)



1900 (2000) (2000) (2000) (2000)

1900 (2000) (2000) (2000) (2000)

1900 (2000) (2000) (2000) (2000)

1900 (2000) (2000) (2000) (2000)

1900 (2000) (2000) (2000) (2000)

1900 (2000)

1900 (2000) (2000) (2000) (2000)

1900 (2000) (2000) (2000) (2000)

1900 (2000) (2000) (2000) (2000)

1900 (2000)

1900 (2000) (2000) (2000) (2000)

1900 (2000) (2000) (2000) (2000)

1900 (2000) (2000) (2000) (2000)

1900 (2000) (2000) (2000) (2000)


1900 (2000) (2000) (2000) (2000)

1900 (2000) (2000) (2000) (2000)

1900 (2000) (2000) (2000) (2000)

1900 (2000) (2000) (2000) (2000)

behave in the same manner if the deflection of the beam is small. In an equivalent solid beam with the same width at every section and the same weight of material at every section. Therefore, the curve of the center of the equivalent girder is equal to the I of the real girder. By plotting the depth of the equivalent girder it can be seen that the curve of its lower chord is approximately parabolic.



With this data it is possible to solve for the moment in the equivalent girder using the frame constant published by the Portland Cement Association. The moment in the equivalent girder will equal the moment in the real girder.

Check girder proportions.


Span.

Design span = 120 Feet

Depth.

Use the same loads as with flange girders. However,

and distributed live load is $1.65 \times 100 = 165$ lb/ft.
 (a) 1.48 ft apart (20 ft apart) - see Fig. 10.10
 (b) 1.65 ft apart (20 ft apart) - see Fig. 10.10



Load	Distance from left end	Reaction at left end	Reaction at right end	Reaction at left end	Reaction at right end
1.48	1.48	304	310.5	304	310.5
64.8	5	304	310.5	304	310.5
61.4	12.5	304	310.5	304	310.5
61.4	15	304	310.5	304	310.5
64.8	18.5	304	310.5	304	310.5
1.48	20	304	310.5	304	310.5
1.48	20	304	310.5	304	310.5
1.48	20	304	310.5	304	310.5

Fixed end moment at left = 180 ft-kips
 Fixed end moment at right = 180 ft-kips

Maximum fixed end moment at right = 180 ft-kips

The 75 lb/ft distributed load is not a live load, but a dead load.

and a negative moment = $1.65 \times 100 \times 10 = 1650$ ft-kips

$$= 1.65 \times 100 \times 10 = 1650$$

$$= 1.65 \times 100 \times 10 = 1650$$

and a negative moment = $1.65 \times 100 \times 10 = 1650$ ft-kips

shear stress at the neutral axis is

$$\tau = \frac{VQ}{Ib} = \frac{1000 \times 1.5 \times 10^3}{100 \times 100} = 150 \text{ psi}$$

shear stress at the top of the web is

$$\tau = \frac{VQ}{Ib} = \frac{1000 \times 1.5 \times 10^3}{100 \times 100} = 150 \text{ psi}$$

shear stress at the bottom of the web is


$$\tau = \frac{VQ}{Ib} = \frac{1000 \times 1.5 \times 10^3}{100 \times 100} = 150 \text{ psi}$$

$$\tau = \frac{VQ}{Ib} = \frac{1000 \times 1.5 \times 10^3}{100 \times 100} = 150 \text{ psi}$$

shear stress at the top of the web is

shear stress at the bottom of the web is


shear stress at the top of the web is



shear stress at the top of the web is

$$\tau = \frac{VQ}{Ib} = \frac{1000 \times 1.5 \times 10^3}{100 \times 100} = 150 \text{ psi}$$


shear stress at the bottom of the web is



shear stress at the top of the web is

$$\tau = \frac{VQ}{Ib} = \frac{1000 \times 1.5 \times 10^3}{100 \times 100} = 150 \text{ psi}$$


1




2




3



4



5



Rotation per inch length = .00000709 radian per inch

Total rotation at mid-span = .00000709 x 60 x 12

$$\times \frac{180}{3.14} = .293 \text{ degrees}$$

Mid-span deflection = 15 x 12 x tan 0.293 = 0.553 inches

Total Stresses.

Web stress = vertical shear + torsional shear

At support = 5220 + 2225 = 7445 psi

At mid-span = 2470 + 2225 = 4695 psi

Flange stress = Bending stress + torsional shear

Combine by principal stresses

$$\begin{aligned} \text{At support} &= \frac{f}{2} + \left(\frac{f^2}{4} + s^2 \right)^{\frac{1}{2}} \\ &= \frac{15300}{2} + \left(\frac{15300^2}{4} + 2225^2 \right)^{\frac{1}{2}} = 15620 \text{ psi} \end{aligned}$$

$$\text{At mid-span} = \frac{16500}{2} + \left(\frac{16500^2}{4} + 2225^2 \right)^{\frac{1}{2}} = 16830 \text{ psi}$$

Girder Deflection Under Design Load.

Assume 100 per cent end restraint at supports and

compute deflection by slope deflection method.

Plot M/I diagram to find its area and center of gravity.


Negative area = $5.478 \frac{\text{kip ft}}{\text{in}^2}$, C.G. = 49.97' from mid-span

Positive area = $6.17 \frac{\text{kip ft}}{\text{in}^2}$, C.G. = 10.06' from mid-span

Moment of M/I diagram = 30500 kip/in

Deflection at mid-span = $\frac{30500}{30000} = 1.015 \text{ ins}$

Usual allowable deflection = $\frac{\text{span}}{300} = \frac{120 \times 12}{800} = 1.8 \text{ ins}$



PLOT OF M/I DIAGRAM
FOR MAIN GIRDER


JUNE 1949

BRIDGE SLAB

In order to resist the bending moment and the applied torque and at the same time allow some horizontal longitudinal movement, it was decided to use a three plate assembly for the end connection which would allow some sliding. The middle plate is the sliding plate and is an enlarged continuation of the bottom flange of the girder. The girder top flange is bent in an arc of 8 foot radius and welded to the sliding plate. The flange fibre stress is thus smoothly transferred to a vertical force. Three web plates are used in the end connection to transfer the shear.

SLIDING PLATE

Design thickness to resist the vertical force of the top flange where it joins the sliding plate.



$$\text{Moment under flange plate} = 0.7 \times 3.825 - \frac{7.15 \times .938^2}{2}$$

$$= 22.46 \text{ in kips}$$

$$\text{required section Modulus} = \frac{22.46}{18} = 1.25 \text{ in}^3$$

$$\text{required thickness} = \frac{(60)^2}{b^2} = \frac{(6 \times 1.25)^2}{1} = 2.75 \text{ in Use 3 inch}$$

MASONRY PLATE

Use a 3/4 inch plate for this plate. The area of bedding is not critical.

SAF PLATES

Use 3 inch plates to give them the same relative stiffnesses as the sliding plate in order to keep a plane surface between them.

ANCHOR BOLTS


Required section modulus to resist bending moment.

Consider concrete bearing area in compression and the bolts in tension. Use bolt tension = 13.5 ksi.

$$S = \frac{7740 \times 1000 \times 12}{13500} = 6880 \text{ ins}^3$$

Neutral Axis of compression concrete and tension steel.

Space $2\frac{1}{2}$ inch bolts as shown. Bolt area = 3.976 in²



Solve for y

$$3 \left[\frac{11(21.65 - y)^2}{2} \right] = 6 \times 3.976(275.75 + 7y) + 2 \times 3.976(139.75 + 2y)$$

y = 0.35 in Assumption for Neutral Axis correct

Moment of Inertia of compression concrete and tension steel.

$$\begin{aligned} I &= 3 \left[\frac{11(21.65)^3}{3} \right] + 23.8(16.35^2 + 28.35^2 + 40.35^2 + 52.35^2 \\ &\quad 64.35^2 + 76.10^2) + 7.95(64.35^2 + 76.10^2) \\ &= 556000 \text{ in}^4 \end{aligned}$$

Section Modulus.

$$S = \frac{556000}{76.10} = 7310 \text{ in}^3 \quad \text{Adequate.}$$

Required Section Modulus to resist torsion.

Consider concrete bearing area in compression and the bolts in tension.

$$S = \frac{803500 \times 12}{13500} = 778 \text{ in}^3$$

Find neutral axis and moment of inertia of concrete and steel by the same method as just described above.

$$I = 315000 \text{ in}^4 \quad c = 66.04 \text{ in}$$

Section Modulus.

$$S = \frac{315000}{66.04} = 4770 \text{ in}^3 \quad \text{Adequate.}$$

BIBLIOGRAPHY

<u>Author</u>	<u>Title and Publisher</u>
Air Reduction	<u>Manual of Design for Air Welded Steel Structures</u> , First Edition; Air Reduction Sales Company; New York; 1946.
American Association of State Highway Officials	<u>Standard Specifications for Highway Bridges</u> , Fourth Edition; American Association of State Highway Officials; Washington, D. C.; 1944.
American Institute of Steel Construction	<u>Bridge Railings, Their Design and Construction</u> ; American Institute of Steel Construction; New York; 1941.
American Institute of Steel Construction	<u>Steel Construction</u> , Fifth Edition; American Institute of Steel Construction; New York; 1946.
American Welding Society	<u>Standard Specifications for Welded Highway and Railway Bridges</u> , Fourth Edition; American Welding Society; New York; 1947.
Amirikian, A.	<u>Analysis of Rigid Frames</u> ; United States Government Printing Office; Washington, D. C.; 1942.
Grinter, L. E.	<u>Theory of Modern Steel Structures</u> , Volume I; The MacMillan Company; New York; 1947.
Kinney, C. S.	<u>Indeterminate Structures</u> ; Masselaer Polytechnic Institute; Troy, N. Y.; 1943.
Lincoln Arc Welding Foundation	<u>Design for Welding</u> ; The James F. Lincoln Arc Welding Foundation; Cleveland, O.; 1943.
Seely, B.	<u>Advanced Mechanics of Materials</u> ; J. Wiley and Sons; New York; 1932.
Timoshenko, S.	<u>Theory of Elasticity</u> ; McGraw-Hill Book Company; New York; 1934.
Watson, W. J.	<u>Bridge Architecture</u> ; W. H. Ralston Inc.; New York; 1927.


BIBLIOGRAPHY


Articles and Papers


- "All-Welded Composite Steel Beam and Concrete Slab Bridges"; Journal of the American Welding Society; May, 1945; pp 435-445.
- "A Symposium on Special Shapes for Welding"; Steel; August 27, 1945; pp 104-107 and 150-154.
- "Most Beautiful Steel Bridges of Last Six Years"; Engineering News-Record; October 7, 1943; pp 14-15.
- "Significant Changes in Modern Bridge Design"; Welds and Abstracts; February 1947; pp 57-60.
- "Special Shapes for Welded Construction"; The Engineer; February 9, 1945; pp 119-120.
- "Special Shapes for Welding Designs"; Steel; July 10, 1944; pp 63-69 and p 130.
- "St. Rose Bridge, Canada"; The Engineer; October 11, 1946; pp 316-317.
- "Torsion of Members Having Sections Common in Aircraft Construction"; Report No. 334, National Advisory Committee for Aeronautics; Sept. of Documents; Washington, D. C.
- "Welded Girder Bridge of Composite Design Carries Deck Area of Two Acres"; Engineering News-Record; December 26, 1946; pp 48-50.
- "Welded Highway Deck Cuts Road Load on Rads Bridge"; Engineering News-Record; January 8, 1948; pp 49-51.

INDEX


<u>Subject</u>	<u>Page</u>
Bridge Seat25, 58-60
Cantilever Beams9, 20, 21, 53-45
Curbing	14, 15, 27
Deflections	
Cantilever Beams21, 43-45
Girder	56
Dimensions	
Bridge Seat	
Cantilever Beams	38
Floor16, 31
Girder7, 23, 46
Stringers18, 34
Floor System9, 16, 17, 31-33
Main Girder.	7, 8, 7, 22-24, 46-56
Railings	14, 15, 28-30
Stresses	
Cantilever Beams42, 43
Floor35
Girder.22, 52, 56
Stringers37
Stringers, Floor	18, 19, 34-37







ELEVATION
Scale: $\frac{3}{16}'' = 1'-0$




ATION
3" = 1'-0

TWO-LANE, 120' SPAN, DECK TYPE
HIGHWAY BRIDGE
PLAN & ELEVATION

DESIGNED BY:


JUNE 1949
SHEET 1 of 4




LONGITUDINAL SECTION



Scale: $\frac{3}{16} = 1'-0"$


SEE DETAIL A






LONGITUDINAL SECTION at A-A
Scale: $\frac{3}{16} = 1'-0$






TYPICAL TRANSVERSE SECTION at B-B

Scale: $\frac{3}{8}" = 1'-0"$




STRINGER SPLICE

Scale: $1\frac{1}{2}" = 1'-0"$



Standard 3" U.S.S. I-BEAM-LOK ARMORED FLOOR
to be installed according to manufacturer's
specifications For details see U.S.S. publication
"LIGHT-WEIGHT STEEL FLOORING," page 69.




SECTIONS & DETAILS

DESIGNED BY:


JUNE 1949

SHEET 2 of 4

TYPICAL GIRDER SECTION
Scale 1"=1'-0"




SECTION at C-C
Scale: 1"=1'-0"




All girder welds shall be done in wandering sequence similar to that shown for LINE A above. Flanges and webs shall be completely fabricated before commencing any longitudinal welding. After proper jiggling, aligning, and tack welding, LINE A shall be welded. Then diaphragm plates shall be installed as much as possible, followed by intermediate stiffeners on one side. LINE B shall then be welded and followed by completing diaphragm plates, and rest of intermediate stiffeners. Girder shall be completed by welding LINES C & D.


WELDING SEQUENCE




ERECTION of FLOOR BEAMS




DETAIL B
Scale: Full Size



GIRDER SECTION at FLOOR BEAMS 1 & 8
Scale: 1" = 1'-0



FLANGE VEE BUTT JOINT




WEB BEVEL BUTT JOINT

DETAILS of BUTT SPLICE WELDS Scale: Full Size


NOTE:
Butt Splice to be made on ground prior to erection. Edges shall be prepared so that downhand welding is used on Vee Joint with only single overhead pass necessary on flanges after cleaning out root of first downhand pass, and root of Bevel Joint is on inside of girder. Weld flanges first using wandering sequence, working from center towards corners, then weld webs similarly.

NOTE:


It is the opinion of the authors that where proper transportation is at all available, the girder should be completely shop fabricated and shipped. If, however, the job site is located where this is not possible, splices shall be used as shown on Sheet 2 and detailed above, and the three girder sections shall each be welded in a sequence similar to the one above for the whole girder.



SPLICE SEGMENT.
This piece shall be fabricated in the field from measurements made on job site after erection of girder.



FLANGE VEE BUTT JOINTS



WEB BEVEL BUTT JOINTS

DETAILS of SEGMENTAL SPLICE

NOTE:
Segmental Splice to be made after girder sections are erected. Edge preparation - see Butt Splice.



TWO-LANE, 120' SPAN, DECK TYPE HIGHWAY BRIDGE

BOX GIRDER DETAILS


DESIGNED BY:


JUNE 1949

SHEET 3 of 4




ELEVATION
Scale: $\frac{3}{4}'' = 1'-0$








SECTION at E-E
Scale: $\frac{1}{4}'' = 1''$



SECTION at F-F
Scale: $\frac{1}{4}'' = 1''$





SECTION at G-G
Scale: $\frac{1}{4}'' = 1''$




PLAN of BRIDGE to ABUTMENT CONNECTION
Scale: $\frac{1}{2}'' = 1'-0$

Sym.
Q

ELEVATION
Scale: $\frac{3}{4}'' = 1'-0''$




WELD DETAIL
Scale: Half Size






WELD DETAILS
Scale: Half Size



PLAN of 3" SLIDING PLATE
Scale: $\frac{3}{4}$ " = 1'-0"

PLAN of BRIDGE to ABUTMENT CONNECTION
Scale: $\frac{1}{2}$ " = 1'-0"



ELEVATION of BRIDGE to ABUTMENT CONNECTION
Scale: $\frac{1}{2}$ " = 1'-0"

TWO-LANE, 120' SPAN, DECK TYPE
HIGHWAY BRIDGE
END CONNECTION

DESIGNED BY:

JUNE 1949

SHEET 4 of 4

DATE DUE

[illegible]

Thesis
C28

Cassidy

10405

The design of an all-
welded, 120' span, two
lane, deck highway
bridge.

F
C

thesC28

The design of an all-welded, 120' span,



3 2768 002 09091 2

DUDLEY KNOX LIBRARY